

PROJECT: METRO CITY MEDICAL CENTER EXPANSION

Drawing Sheet: A-101 | Discipline: Architectural (CSI Division 01 & 09) | Revision: Rev 1 — Issue for Bid

Architect of Record:	Perkins & Will Commercial Architects	Date:	August 12, 2026
General Contractor:	Turner / Mortenson Joint Venture	Gross Area:	145,000 GSF
Bid Package:	BP-03 Architectural Interiors & Partitions	Target Bid Date:	September 15, 2026

1. ARCHITECTURAL ROOM & WALL SCHEDULE (LEVEL 1 PODIUM)

Room #	Room Name	Area (SF)	Wall Type	Acoustical STC	Finish Spec
101	Emergency Triage A	450 SF	Type W4 (2-Hr Rated)	STC 55 Sound Bead	09 29 00 Gypsum Board
102	Trauma Suite 1	720 SF	Type W5 Lead Lined	STC 60 Lead Shielded	13 49 00 Radiation Shielding
103	Imaging / CT Scan	680 SF	Type W5 Lead Lined	STC 60 Acoustical	13 49 00 Lead Glass Viewports
104	Clean Supply Core	320 SF	Type W2 Standard	STC 45 Perimeter Bead	09 91 23 Antimicrobial Paint
105	Staff Breakroom	540 SF	Type W1 Partition	STC 45 Sound Insulation	09 65 00 Resilient Flooring

2. SPECIFICATION DISCREPANCY & SCOPE NOTES (KEYNOTES)

- **KN-01:** Floor plan callout tag A-14 requires UL Design U465 perimeter sound sealant beads at all 2-hour corridor demising partitions.
- **KN-02:** Ceiling height is 10'-0" AFF in corridors, 9'-0" AFF in patient treatment areas. Gypsum board ceiling assemblies per Spec Section 09 22 16.
- **KN-03 (Addendum Note Δ1):** Add acoustic damping baffles above ceiling grid along grid lines 4 through 8.